

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22282-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 26-9S-21W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: COX C Well #: 1
County: GRAHAM Total Vertical Depth: 3849 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: PO BOX 27710
DENVER, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217	0	158 SX
PROD	5.5	3848	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2010 9:30 AM
Plug Co. License No.: 34093 Plug Co. Name: SUMMIT WELL SERVICE LLC
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 425-7387

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
DV Tool at 1722' w/375 sxs.
Perfs at 3790' - 3812'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: PARTIAL
Date/Time Plugging Completed: 06/25/2010 11:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3716' - pumped 100 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 2290' - pumped 175 sxs 60/40 pozmix - 4% gel with 400# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus.
Max. P.S.I. 300#.

Perfs:

Top	Bot	Thru	Comments
3808	3812		
3806	3808		
3790	3794		

INVOICED
DATE 10-14-2010
INV. NO. 2011060040

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #41544.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM


JOHN B. COLLINS
2911 CANTERBURY
HAYS, KS. 67601

#1 COX C

26-9-21W
SW NW NE

CONTR JAY-LAN CORPORATION CTY GRAHAM

GEOLOG LAWRENCE GRAY FIELD MOREL



ELV 2281 KB SPD 12/23/85 CARD ISSUED 3/13/86 IP P 25 BO & 575 BWPD
2274 GL DRLG COMP 1/6/86 ARB 3808-3812

LOG	Tops	Depth/Datum	API 15-065-22,282
ANH		1730+ 551	8 5/8 " 217 / 158SX, 5 1/2 " 3848 / 500SX
TOP		3234- 953	NO CORES OR DST'S
HEEB		3441-1160	MICR - CO, PF (ARB) 3790-3794, W / 2 SPF, NON-COMMERCIAL,
TOR		3463-1182	PF (ARB) 3806-3808, W / 2 SPF, NON-COMMERCIAL, SQZD ALL
LANS		3480-1199	PFS W / 100SX; PF (ARB) 3808-3812, W / 2 SPF, AC 250 GAL
BKC		3699-1418	(15% MA), SO, POP, P 25 BO & 575 BWP, 2/7/86
ARB		3787-1506	
RTD		3849-1568	

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS