

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23561-00-00
Spot: SWSENWNW Sec/Twnshp/Rge: 12-13S-13W
1170 feet from N Section Line, 890 feet from W Section Line
Lease Name: DAUBER B Well #: 1
County: RUSSELL Total Vertical Depth: 3100 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	558	0	250 SX
T1	2.375	3069		
PROD	5.5	3097	1793	80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2010 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls.
Cut casing at 1793'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2010 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded back to 2850' - topped off with 5 sxs cement - 07/13/2010.
Pulled casing to 1400' - pumped 100 sxs cement with 200# hulls.
Pulled casing to 625' - pumped 80 sxs cement with 100# hulls.
Pulled casing to 150' - pumped 45 sxs cement - cement circulated.
POOH. Topped off with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2894	2897		LANSING 'F'

INVOICED
DATE 10-18-2010
INV. NO. 2011060044

Remarks: QUALITY OIL WELL CEMENTING-TICKET #4090.

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

JUL 22 2010

JUL 19 2010

KCC WICHITA

JOHN O FARMER
RUSSELL KS 67665-2635

#1 DAUBER B

12-13S-13W
1170'FNL & 890'FWL, SEC
KANSAS

City: RUSSELL **Spot:** SW SE NW NW **API:** 15-167-23561
Site: 4-3/4 N & 3/4 W OF BUNKER HILL KS **Lat/Long:** 38.94029 -98.72139
Field: BACKWATER EXT (1/4 S)

FR: 02/02/2009 **Spd:** 02/05/2009 **Drig Cp:** 02/11/2009 **Issued:** 07/20/2009 **Revised:** 07/20/2009

Copyright 2009 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

OIL, LKC, INTV NA, 5/15/2009

Contr: DISCOVERY DRILLING #2

Geol: BRAD J. HUTCHISON

Elev: 1609 KB, 1601 GL, 1607 DF

Formation Tops: (L-Log, S-Sample, D-Driller)

NO TOPS RPTD

LOGGED

LTD 2984 -1375

PBTD 3073 -1464

RTD 3100 -1491

Csg: 8-5/8" 558 / 260 SX (ALT 1), PROD CSG NA

Finds:

COMMENT: PROPOSED START 2/7/2009; MI &

RURT 2/5/2009

NO CORES

DSTS TAKEN - DETAILS NA

Comp Info: TRGT ZN: LKC, ARB (OIL), PTD 3400

(ARB), MICT (2/26/2009) - CO, PB 3073, PF (LANS F)

INTV NA, GSO, POP, OIL WELL (POTENTIAL NOT
RPTD), 5/15/2009 - TIGHT HOLE - NO OTHER
INFO AVAILABLE - TEMP COMP 7/20/2009