

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23344-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 31-7S-21W
520 feet from N Section Line, 1170 feet from E Section Line
Lease Name: VAN LOENEN B Well #: 1
County: GRAHAM Total Vertical Depth: 3740 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221	0	160 SX CMT.
T1	2.375	3698		
PC		1768		450 SX CMT.
PROD	5.5	3738	0	160 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/09/2010 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DUANE EICKMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-3144

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Port collar at 1768' w/450 sxs.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2010 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3670' - pumped 100 sxs cement with 250# hulls.
Pulled tubing to 2700' - pumped 100 sxs cement with 100# hulls.
Pulled tubing to 1750' - pumped 135 sxs cement - circulated.
Pulled tubing out - tied onto backside - squeezed with 10 sxs cement.
S.I.P. 200#.
Topped off 5 1/2" with 15 sxs cement.
Plug complete.

Perfs:

Top	Bot	Thru	Comments
3683	3692		ARBUCKLE

Remarks: ALLIED CEMENTING COMPANY-TICKET #41662.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

RECEIVED

JUL 15 2010

KCC WICHITA

JUL 12 2010

INVOICED
DATE 10-18-2010
INV. NO. 2011060044

N O FARMER
SELL KS 67665-2635

31-07S-21W
520'FNL & 1170'FEL, SEC
KANSAS

#1 VAN LOENEN B

GRAHAM
3 N & 3/4 W OF BOGUE KS
HOLSMAN EXT (1/4 N)

Spot: SW NW NE NE API 15-065-23344
Lat/Long: 39.40710 -99.69993

19/04/2007 Spd: 09/20/2007 Drig Cp: 09/26/2007 Issued: 01/21/2008 Revised: 01/21/2008

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

atus:
ARB, INTV NA, (NEW PAY), 12/1/2007
r: WW DRILLING #8
BRAD HUTCHISON
2176 JB

(POTENTIAL NOT RPTD), 12/1/2007 - (NEW PAY) -
TIGHT HOLE - NO OTHER INFO AVAILABLE - TEMP
COMP 1/21/2008

ation Tops: (L-Log, S-Sample, D-Driller)

NO TOPS RPTD
LOGGED
PBD 3708 -1532
RTD 3740 -1564
3-5/8" 221 (ALT 2), PROD CSG NA, PORT COLLAR
68 / 450 SX

MENT: PROPOSED START 9/10/2007; MI &
9/19/2007

DRES OR DSTS RPTD

Info: TRGT ZN: LKC, ARB (OIL), PTD 3820
, MICT (10/16/2007) - CO, PB 3708, PF (ARB)
NA, SWB DWN, GSO, POP, OIL WELL