

4-110077

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-02,171 0000

SE NE SE /4 SEC. 14 11 S, 17 W
1650 feet from S section line
330 feet from E section line

1/3/00

Operator license# 7064

Lease: Henry Mai Well # 7

Operator: Cattleman's Oil Operations

County: Ellis 109.23

Address: 2260 Catherine Road
HC 39 - Box 74
Hays, Kansas 67601

Well total depth 3361 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 13 Inch @ 129 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Cattleman's Oil Operations License# 7064

Address: 2260 Catherine Road - Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 3 Month: January Year: 2000

Plugging proposal received from: Leo Dorzweiler

Company: Cattleman's Oil Operations Phone: 785-625-5394

Were: Plug according to KCC Rules & Regulations.
Ordered 250 sxs cement - plug thru tubing.
Perfs at 3048' - 3050'; 3202' - 3206'; 3248' - 3250'; 3270' - 3273';
3292' - 3295'.

Plugging Proposal Received by: Roger Moses

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00 A.M., Day: 3, Month: January, Year: 2000

Actual plugging report: 13" S.P.set at 129' w/ 90 sxs cmt. 5 1/2" casing at 3359' w/890 sxs.
Perf at 950' and squeezed with 405 sxs cement. Ran tubing to 1500' and pumped 200 sxs cement
with 500# hulls. Pulled tubing to 900' and circulated with 30 sxs cement. Pulled all
tubing - hole full of cement. Tied to annulus - immediate pressure of 1000# - took no
cement. Total of 230 sxs 60/40 pozmix with 10% gel and 500# hulls.

INVOICED

DATE 1/31/00

INV. NO. 061189

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING . Elevation: 1845 GL

I did[X] / did not[] observe the plugging.

Roger Moses
STATE CORPORATION COMMISSION
Form CP-2/3

JAN 31 2000
01-31-00
CONSERVATION DIVISION
Wichita, Kansas

R



Specific Well--MAI 7

All Well Data

API:	Location: T11S R17W, Sec. 14, SE NE SE	Total Depth: 3361
Operator: GULF	Longitude: -99.16785	Formation:
Field:	Latitude: 39.09395	
Lease: MAI, Well 7	Spud Date:	
County: Ellis	Completion Date:	

Cuttings Data

Box Number: 06331
Times Checked Out: 0
Starting Depth: 2700 ; Ending Depth: 3360
Skips:

Kansas Geological Survey, Oil and Gas Well Database

Comments to webadmin@kgs.ukans.edu

URL=<http://magellan.kgs.ukans.edu/Qualified/index.html>

Well Log Programs Updated Nov. 15, 1999. Data added continuously.