

4-110076

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-02,172 0000

C S2 NW SE /4 SEC. 14 11 S, 17 W  
1650 feet from S section line  
1980 feet from E section line

1/3/00

Operator license# 7064

Lease: Henry Mai Well # 8

Operator: Cattleman's Oil Operations

County: Ellis 109.20

Address: 2260 Catherine Road  
HC 39 - Box 74  
Hays, Kansas 67601

Well total depth 3360 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 13 Inch @ 120 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Cattleman's Oil Operations License# 7064

Address: 2260 Catherine Road - Hays, Kansas 67601

Company to plug at: Hour: 11:00 A.M. Day: 3 Month: January Year: 2000

Plugging proposal received from: Leo Dorzweiler

Company: Cattleman's Oil Operations Phone: 785-625-5394

Were: Plug according to KCC Rules & Regulations.  
Ordered 250 sxs cement - plug thru tubing.

Plugging Proposal Received by: Roger Moses  
Plugging operations attended by agent? All , Part , None

Completed: Hour: 3:00 P.M., Day: 3, Month: January, Year: 2000

Actual plugging report: 13" S.P.set at 120' w/100 sxs cmt. 5 1/2" casing at 3360' w/111 sxs.  
Squeezed at 1055' w/459 sxs. Ran tubing to 1500' and pumped 110 sxs cement with 300# hulls.  
Pulled all tubing and tied to 5 1/2" casing and pumped 115 sxs cement - casing full.  
Annulus took no cement. Total 225 sxs 60/40 pozmix with 10% gel and 300# hulls.

INVOICED

DATE 1/31/00

INV. NO. 061189

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 1837 GL

I did  / did not  observe the plugging.

Roger Moses  
Agent  
STATE CORPORATION COMMISSION  
Perm CP 2/3

IAN 31 2000  
1-31-00  
CONSERVATION DIVISION  
Wichita, Kansas

GULF OIL CORP

#8 HENRY MAT

14-11-17W

CS2 NW SE

Contr.

ELLIS County

E 1842

Comm. 1-17-40

Comp. 2-23-40

IP

2348 BOPD

Tops	Depth	Datum
ANH	1051	
ARB	3359	
TD	3366	

Casing  
 12" 130  
 5" 3360

A/1000  
 2800' OIH: Swb 44 BOPH


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS