

4-28-88

6 040879

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 15-051-22014-0000

N/2 S/2 SE, SEC. 14, T 11 S, R 17 W

990 feet from S section line
1320 feet from E section line
ANB KCC

TECHNICIAN'S PLUGGING REPORT

Operator License # 7064

Lease Name Mai Well # 11

Operator: Cattleman's Oil Oper.
Name & Address: HC 39 Box 74
Hays, Ks. 67601

County Ellis 109.87
Well Total Depth 3339 3359 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 241 w/110

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 28 Month: April Year: 19 88

Plugging proposal received from Leo Dorzweiler
(company name) C.O.O. (phone) _____

were: 5 1/2" casing set @ 3358' w/ 150 sx, Perfs @ 2500', 1800', 1500', 1200', 1000', 600',
400', 300'. Recovered 300' of 5 1/2" casing. Perfs @ 2955' to 3280'. Plug bottom w/ sand
to 2900', plus 5 sx cmt on sand per Gilbert Scheck. Ordered 200 sx 65/35 pozmix, 10% gel,
w/ 1/4# flocele per sx, plus 6 sx hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:10Pm Day: 28 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 8 5/8" SP W/200 sx cmt, w/ 1/4 # flocele plus 6 sx
hulls mixed in w/ 1st 60 bbls of slurry. Maximum psi 400#. Shut in psi 100#.

RECEIVED
STATE CORPORATION COMMISSION
07-06-88
JUL 6 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
DATE 7-7-88
INV. NO. 21200

Signed Dennis L. Hamel
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas