

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00933-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 21-1S-18W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: JACKSON G Well #: 3
County: PHILLIPS Total Vertical Depth: 3540 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	198	0	175 sxs
PROD	5.5	3539	0	175 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2010 10:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Casing collapsed or parted at 1793'. Unable to get below 1793'.
No squeeze records. Perforated two holes at 1350' and 190'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2010 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

L-K perforated two holes at 1350' and 190'.
Ran tubing to 1760'. Allied pumped 170 sxs 60/40 pozmix - 4% gel - circulated cement.
PTOH. Allied pumped 35 sxs cement down 5 1/2" casing - blew holes in 5 1/2" casing above Braden head.
Waited on welder. Welded casing patch.
Allied pumped 15 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Hooked up to backside and pumped 50 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3478	3482		
3454	3458		
3436	3440		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

INVOICED
DATE: 10/21/10
INV. NO. 211060123
RECEIVED
OCT 18 2010
KCC WICHITA

OCT 13 2010