

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-00087-00-00  
Spot: N2NWSWSE Sec/Twnshp/Rge: 8-33S-27W  
1261 feet from S Section Line, 2316 feet from E Section Line  
Lease Name: THIESSEN Well #: 1  
County: MEADE Total Vertical Depth: 5840 feet

Operator License No.: 30417  
Op Name: AEXCO PETROLEUM, INC.  
Address: 1600 BROADWAY, STE 2250  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5590		WITH 2 SX CMT
SURF	8.625	1403		WITH 850 SX CMT
COND	20	75		
PROD	5.5	5833	2420	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/25/2010 1:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT ON BOTTOM. 1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/25/2010 5:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SET CIBP @ 5590' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5714	5718		MORROW
5709	5712		MORROW
5695	5699		MORROW
5690	5692		MORROW

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060079

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

RECEIVED  
AUG 31 2010  
KCC DODGE CITY

Signed Jerry W. Stapleton  
(TECHNICIAN)  
PART II

RECEIVED  
SEP 07 2010

KCC WICHITA