

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21235-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 4-15S-29W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: DEAN Well #: 3
County: GOVE Total Vertical Depth: 4330 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	271	0	175 SX
PROD	4.5	4068	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2010 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES CORPORAT Phone: (620) 793-2146

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 200# hulls - 6 sxs gel.
PBTD 4068'. Port collar 1806' w/325 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2010 12:32 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 4 1/2" casing - pumped 75 sxs cement with 200# hulls - followed with 6 sxs gel - followed with 65 sxs cement.
Shut in at 100# P.S.I.
Tied onto backside - pumped 75 sxs cement.
Shut in at 150# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3926	3930		LKC


INVOICED
DATE 10-14-2010
INV. NO. 2011060081

Remarks: SWIFT CEMENTING COMPANY-TICKET #18104.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

SEP 20 2010

Form CP-2/3

SEP 15 2010

KCC WICHITA