

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23382-00-00  
Spot: W2W2NW Sec/Twnshp/Rge: 30-16S-21W  
3944 feet from S Section Line, 4965 feet from E Section Line  
Lease Name: SUNLEY Well #: 1  
County: NESS Total Vertical Depth: 4370 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	262		WITH 170 SX CMT
PC		1663		WITH 335 SX CMT
PROD	5.5	4372	0	WITH 500 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/30/2010 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: THAD STARR, PRODUCTIO Company: AMERICAN ENERGIES CORPORAT Phone: (620) 793-2146

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP GEL SPACER FOLLOWED BY 35 SX CMT. PULL TBG TO 1650' & CIRCULATE 5 1/2" FULL OF CMT. PULL TBG & TOP OFF 5 1/2". PRESSURE 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CEMENT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/30/2010 12:17 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 4208' & PUMPED 18 SX GEL & 35 SX CMT. PULLED TBG TO 1665' & PUMPED 190 SX CMT CIRCULATING CMT TO SURFACE. PULLED TBG OUT OF HOLE. TOPPED OFF 5 1/2" WITH 10 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED

SEP - 3 2010

KCC DODGE CITY

RECEIVED

SEP 14 2010

KCC WICHITA

Form 1523

INVOICE  
DATE 10-14-2010  
INV. NO. 2011060081