

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23677-00-00
Spot: NESENW Sec/Twnshp/Rge: 30-16S-21W
3813 feet from S Section Line, 2990 feet from E Section Line
Lease Name: SUNLEY Well #: 3
County: NESS Total Vertical Depth: 4330 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	333		WITH 155 SX CMT
PC		1615		WITH 375 SX CMT
PROD	5.5	4329	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2010 12:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: THAD STARR, PRODUCTIO Company: AMERICAN ENERGIES Phone: (620) 793-2146

Proposed Plugging Method: PUMPED DOWN 5 1/2" WITH 200# HULLS - 35 SX CMT - GEL SPACER TO 1600' & CMT FROM 1600' TO 0'.
PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2010 1:22 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED DOWN 5 1/2" WITH 200# HULLS - 50 SX CMT - 18 SX GEL - 135 SX CMT.
MAXIMUM PRESSURE 400 PSIG. SHUT IN PRESSURE 400 PSIG. PRESSURED 8 5/8"
X 5 1/2" ANNULUS WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4224	4227		

INVOICED
DATE: 10-14-2010
INV. NO. 2011060081

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey
(TECHNICIAN)

RECEIVED

SEP - 3 2010

KCC DODGE CITY

RECEIVED

SEP 07 2010

KCC WICHITA

Form CB-2/3