

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22206-00-00
Spot: SWNESW Sec/Twnshp/Rge: 11-7S-23W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HALE Well #: 1
County: GRAHAM Total Vertical Depth: 4164 feet

Operator License No.: 30076
Op Name: ANDERSON, ANDY DBA A & A PRODU
Address: PO BOX 100
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261	0	170 SX
PROD	4.5	4140	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2010 10:00 AM
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: ANDY ANDERSON Company: A&A PRODUCTION Phone: (785) 567-8068

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Well was two staged at 2080' w/150 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2010 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3500' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 2500' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls - circulated to surface.
Pulled all tubing. Topped off 4 1/2" casing with 20 sxs 60/40 pozmix - 4% gel.
Visually checked 8 5/8" x 4 1/2" annulus. Cement to surface.

Perfs:

Top	Bot	Thru	Comments
4019	4028		
3834	3840		

INV 01030
DATE 10-14-2010
WELL NO. 2011060083

Remarks: ALLIED CEMENTING COMPANY-TICKET #41558.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

JUL 29 2010

JUL 26 2010

KCC WICHITA

GREAT EASTERN ENERGY &
 DEVELOPMENT CORPORATION
 5660 S. SYRACUSE CIRCLE #1 HALE
 ENGLEWOOD, CO 80111

11-7-23W
 SW NE SW

CONTR STOEPPELWERTH DRILLING CTY GRAHAM

GEOLOGICAL JOHN GREEN FIELD WC(1/8 E OF MT ETNA
 ABD)

ELV 2404 KB SPD 6/25/85 ^{CARD ISSUED} 10/10/85 IP P 25 BOPD, NW
2399 GL ORLG COMP 7/2/85 LKC 3834-3840



LOG	Tops	Depth/Datum
SC	2082	+ 322
HEEB	3638	-1234
LANS	3683	-1279
BKC	3875	-1471
REW ARB	4071	-1667
SOL ARB	4084	-1680
RTD	4164	-1760

API 15-065-22,206
 8 5/8 " 261 / 170SX, 4 1/2 " 4140 / 175SX
 DST (1) 3738-87 (LKC) / 15-30-60-120, REC 130' OIL SPKD, M,
 SIP 1276-1266#, FP 51-51 / 72-103#, HP 1881-1799# BHT
 107°
 DST (2) 3790-3842 (LKC) / 10-15-60-120, 960" GIP, REC 900'
 GSY OIL, 120' OCM, SIP 1286-1256#, FP 114-145 / 197-383#,
 HP 1952-1942#, BHT 108°
 MICT - CO, PF (PENN CONG) 4019-28, W / 2 SPF, AC 500G (15%
 NE), SWB DWN, SET CIBP AT 3920, PF (LKC) 3834-40, W / 2
 SPF, AC 500G (15% REG), SWB DWN, RE-AC 1500G (15% REG),
 SWB DWN, GSO, POP, P 25 BOPD, NW, 7/26/85

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS