

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20116-00-00  
Spot: S2SENE Sec/Twnshp/Rge: 32-14S-12W  
3092 feet from S Section Line, 794 feet from E Section Line  
Lease Name: BORELL TWIN Well #: 1  
County: RUSSELL Total Vertical Depth: 3167 feet

Operator License No.: 30081  
Op Name: ANSHUTZ, EVELYN DBA ANSHUTZ OI  
Address: PO BOX 274  
ELLSWORTH, KS 67439

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	241	0	w/175 sxs cmt
LI	3	2450		
PROD	4.5	3165	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/06/2010 4:30 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LARRY DOLECHEK Company: ANSHUTZ OIL Phone: (785) 658-3528

Proposed  
Plugging  
Method:

Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Perf: 650' - 1000'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/06/2010 6:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked up to 3" liner and pumped 20 BBLs of water.  
Pumped 275 sxs cement with 450# hulls.  
Max. P.S.I. 450#. S.I.P. 0#.  
Braden head was full of cement.  
08/09/2010 - Checked top of cement 60' down from surface.  
Topped off with 3 sxs cement.

Perfs:

INVOICE  
DATE 10-14-2010  
TRK NO. 2011060084

Remarks: ALLIED CEMENTING COMPANY-TICKE #48144.

Plugged through: CSG

RECEIVED  
AUG 18 2010  
KCC WICHITA

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

AUG 10 2010

JAMES W. HERSHBERGER #1 BORELL (TWIN) 32-14-12W  
 100' N & 100' W  
 C S/2 SE NE

Contr. OMEGA DRLG Cty. RUSSELL

Geol. Pool HALL-GURNEY

E. 1723 KB Cm. 10/6/67 Cp. 11/30/67 IPP 74.17 BOPD, NW  
 ARB 3165 $\frac{1}{2}$ -67


API 15-167-20,116

SMP Tops	Depth	Datum	Csg.
			8" 241/175 sx, 4" 3165 $\frac{1}{2}$ /125
ANHY	650	+1073	DST 2900-75/1'15", 420' GIP, 240' HOCM, 120' SOCM, 480' MSW, BHP 1161-1116#, FP 67-440#
HEEB	2787	-1064	
BRLM	2869	-1146	DST 3034-66/1', 85' MW, BHP 1064-63#, FP 24-54#
LANS	2880	-1157	
ARB	3164	-1441	DST 3152-3167/1', 2040' OIL, 120' OCM, BHP 1053-1044#, FP 76-828#
RTD	3167	-1444	COTD 3167, FU 2800' OIL, NW/12 HRS, PMP 74.17 BO/24 HRS, NW.

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS