

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21632-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 28-27S-11W
367 feet from S Section Line, 4642 feet from E Section Line
Lease Name: BARKER Well #: 1
County: PRATT Total Vertical Depth: 4802 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3900		WITH 5 SX CMT
SURF	8.625	725		WITH 675 SX CMT
PROD	5.5	4522	1975	WITH 250 SX CMT

Well Type: SWD UIC Docket No: D24238.0 Date/Time to Plug: 08/04/2010 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3900' & 5 SX CMT. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/04/2010 11:05 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

FIBERGLASS TBG FISH @ 3960'. TOC @ 3272 SET CIBP @ 3900' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 752' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4516	4800	OH	ARBUCKLE

INVOICES
DATE: 10-14-2010
INV. NO. 2011060085

Remarks: USED 60/40 POZMIX 2% GEL 2% CC BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
AUG -6 2010
KCC DODGE CITY

RECEIVED
AUG 10 2010
KCC WICHITA

Form CP-2/3