

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21495-00-00
Spot: S2NESE Sec/Twnshp/Rge: 30-9S-22W
1659 feet from S Section Line, 660 feet from E Section Line
Lease Name: FARRELL Well #: 1
County: GRAHAM Total Vertical Depth: 3940 feet

Operator License No.: 4868
Op Name: ASHER ASSOCIATES, INC.
Address: 2350 E WILLIAMETTE LN
GREENWOOD VILLAGE, CO 80121

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210	0	165 SX
T1	2.375	3863		
PROD	4.5	3915	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2010 5:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ROY CASE Company: ASHER ASSOCIATES, INC. Phone: (785) 628-6859

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Bad casing at 1374'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2010 7:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran bit to 1374'. Casing parted - out of hole. Drilled to 1527'.
Pulled bit. Ran back tubing - open ended - could not get below 1374'.
Allied pumped 105 sxs 60/40 pozmix - 4% gel - circulated cement.
PTOH. Allied pumped 175 sxs 60/40 pozmix - 4% gel with 400# hulls.
Max. P.S.I. 1200#. S.I.P. 450#.
Backside pumped 85 sxs cement with 100# hulls.
Max. P.S.I. 250#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3810	3814		LKC
3788	3793		LKC
3651	3882		LKC

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

10-14-2010
2011060086
RECEIVED
AUG 23 2010
KCC WICHITA

ARROWHEAD PETROLEUM INC
 P.O. BOX 8287 MUNGER ST #1 FARRELL 30-9-22W
 WICHITA, KS 67208 C S/2 NE SE
 CONTR BIG SPRINGS DRLG INC CTY GRAHAM
 GEOL BRUCE REED FIELD RED LINE NW

E 2399 KB CM 10/4/81 CARD ISSUED 2/11/82 IP P 20 BOPD & WTR
 API 15-065-21,495 LANS 3846-50

+	+
+	+
+	+

LOG	TOPS	DEPTH	DATUM
ANH	1926	+ 473	
B/ANH	1963	+ 436	
TOP	3393	- 994	
HEEB	3615	-1216	
TOR	3638	-1239	
LANS	3651	-1252	
MUN CR	3772	-1373	
B/KC	3882	-1483	
LTD	3936	-1537	
RTD	3940	-1541	

8 5/8" 210/165sx; 4 1/2" 3915/125sx
 DST (1) 3733-3760/30-45-60-45, REC
 196' MW. W/O SPTS, SIP 613-596#,
 FP 55-77/99-154#
 DST (2) 3840-3864/30-45-30-45, REC
 5' DM, SIP 556-580#, FP 33-33/33-33#
 MICT - CO, PF 8/3846-50, AC 1750G, SWE
 5 BFPH 85% O, POP, P 20 BOPD & WTR,
 2/1/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS