

15-167-30167-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

RUSSELL County. Sec. 4 Twp. 13 Rge. (E) 15 (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SW

Lease Owner JAY-BEE OIL COMPANY, INC.

Lease Name MERMIS Well No. 1

Office Address UNION CENTER BLDG., WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed MARCH 12, 1966

Application for plugging filed (3-12-66 PHONE) MARCH 15, 1966

Application for plugging approved MARCH 12, 1966


Plugging commenced MARCH 12, 1966

Plugging completed MARCH 12, 1966

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	334'	8-5/8"	334'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD. PRESSURED UP ON SURFACE PIPE TO 200 LBS. SQUEEZED WITH 90 SACKS CEMENT. JOB DONE BY GLOBE CEMENTING CO. PUMP TRUCK. JOB COMPLETE @ 1:30 AM MARCH 12, 1966.

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1966
03-23-1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.

Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. E. E. HALL

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

514 ORPHEUM BLDG., WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 15TH day of MARCH, 1966

My commission expires FEB. 1, 1968

Barbara J. Layton
BARBARA J. LAYTON Notary Public.

15-167-30167-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

MERMIS #1
 NW NW SW SECTION 4-13S-15W
 RUSSELL COUNTY, KANSAS

COMMENCED: MARCH 2, 1966
 COMPLETED: MARCH 11, 1966

OPERATOR - JAY-BEE OIL COMPANY, INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	260	SHALE AND SAND	
260	285	SAND	
285	292	SHALE	
292	327	SAND	
327	334	SHALE	
334	380	SAND	
380	595	SHALE AND RED BED	
595	605	RED BED AND IRON	
605	675	SHALE	
675	838	SHALE AND RED BED	
838	875	ANHYDRITE	
875	1575	SHALE	
1575	2120	SHALE AND LIME	
2120	2285	SHALE	
2285	2600	SHALE AND LIME	
2600	2735	SHALE	
2735	2916	LIME AND SHALE	
2916	3212	LIME	
3212	3226	ARBUCKLE	
3226	TO		

RAN 17 JOINTS OF 8-5/8" CASING,
 SET @ 324' W/ 225 SACKS CEMENT.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 23 1966
 03-23-1966
 CONSERVATION DIVISION
 Wichita, Kansas

DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NW NW SW SECTION 4-13S-15W, RUSSELL COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 15TH DAY OF MARCH, 1966 PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HERETO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.