

15-167-00449-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Russell County. Sec. 3 Twp. 13 Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE

Lease Owner Clarence Wilhelm

Lease Name Zimmerman Well No. 1

Office Address 316 Grant, Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-26-60 19

Application for plugging filed 10-26-60 19

Application for plugging approved 10-26-60 19

Plugging commenced 10-26-60 19

Plugging completed 10-26-60 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3189 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	227'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/4 sack of hulls, wooden plug set at 215'.
Mixed 25 sacks cement through drill pipe.

1/2 sack of hulls, wooden plug set at 40'.
Mixed 10 sacks cement.

RECORDED
STATE CORPORATION COMMISSION
11-NOV-7
CONS. DIV.
WICHITA, KANSAS
07-1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address P.O. Box 97, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Donald D. Vaughan

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Donald D. Vaughan
Donald D. Vaughan

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 1960

My commission expires May 19, 1962

Norris Taylor
Norris Taylor Notary Public.



WELL LOG

Clarence Wilhelm
567 East Fourth
Russell, Kansas

#1 Zimmerman
NW SW SE Sec. 3-13S-15W
Russell County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 10-17-60
Completed: 10-26-60
D & A

Casing Record: 8-5/8" at 227' with 165 sacks HA5 Quickset Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Shale & Sand	0	227'	1682' Gr.
Hard Lime	227'	295'	1684' D.F.
Shale & Shells	295'	650'	1687' K.B.
Redbed	650'	753'	
Anhydrite	753'	791'	
Shale & Shells	791'	1510'	
Lime & Shale	1510'	2025'	
Shale with Lime Streaks	2025'	2605'	
Lime	2605'	2824'	
Shale & Lime	2824'	2873'	
Lime	2873'	3138'	
Conglomerate	3138'	3189'	
Total Depth	3189'		

<u>FORMATION TOPS</u>	
Anhydrite	753' (+934)
Heebner	2824' (-1137)
Toronto	2844' (-1157)
Lansing-Kansas City	2873' (-1186)
Conglomerate	3138' (-1451)

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW SW SE Sec. 3-13S-15W, Russell County, Kansas to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 28th day of October, 1960.

My commission expires October 3, 1964.

Helen E. Fischer
Helen E. Fischer, Notary Public

