

15-167-00650-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 3 Twp. 13 Rge. 15 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE
Lease Owner Anschutz Oil Company, Incorporated
Lease Name Zimmerman Well No. 1
Office Address Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 7 19 63
Application for plugging filed " 19 "
Application for plugging approved " 19 "
Plugging commenced " 19 "
Plugging completed " 19 "

Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3315 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-----|-------|--------|------------|
| | | 0 | 171 | 8 5/8 | 171 | -0- |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled w/heavy mud to 350', 1/2 sck.
hulls, 20 sks. cement. Mud to 160', 1/4
sck. hulls, 20 sks. cement. To 40' 1/2 sck.
hulls and 10 sks. cement through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1963
09-13-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Terrel Drilling and Producing
Address Box 606, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Joe K. Branum (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
Box 606, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of September, 19 63

My commission expires 12-12-66

Notary Public.

15-167-00650-00-00

W E L L L O G

OPERATOR: Anschutz Oil Co., Inc.
Wichita Plaza Building
Wichita, Kansas

CONTRACTOR: Terrel Drilling & Producing
Box 606
Russell, Kansas

LEASE: Zimmerman #1

COMMENCED: August 29, 1963

LOCATION: NE NE Sec. 3-13-15W
Russell County, Kansas

COMPLETED: September 7, 1963

DEPTHS & FORMATIONS

| | | | |
|----------------------|------|----------------------|------|
| Clay & Postrock | 168 | Shale & Lime | 2385 |
| Shale | 240 | Shale & Lime Streaks | 2550 |
| Red Bed | 450 | Shale & Lime | 2695 |
| Shale & Sand | 595 | Lime & Shale | 3023 |
| Red Bed | 878 | Lime | 3040 |
| Anhydrite | 910 | Lime & Shale | 3100 |
| Shale & Shells | 1200 | Lime | 3235 |
| Red Bed | 1500 | Lime & Shale | 3277 |
| Shale w/Lime Streaks | 1595 | Lime & Arbuckle | 3287 |
| Lime & Shale | 2175 | (R.T.D.) | 3315 |

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1963
09-13-1963
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)
COUNTY OF RUSSELL) ss

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: "That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct."

Joe K. Branum
Joe K. Branum - TERREL DRILLING & PRODUCING

Subscribed and sworn before me this 10th day of September, 1963.



L. Lee Simpson
Notary Public Russell County

My Commission Expires: 12-12-66