

15-167-00483-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Russell County. Sec. 4 Twp. 13 Rge. (E) 15(W)

Location as "NE/CNW&SW¼" or footage from lines SE NW NW

Lease Owner A. F. Schmidt

Lease Name Mermis "C" Well No. 1

Office Address Box 662 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed Feb. 26 19 60

Application for plugging filed Feb. 29 19 60

Application for plugging approved 19

Plugging commenced 3:45 p.m. Feb. 26 19 60

Plugging completed 8:30 " " " 19 60

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Leiker

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3310 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	232'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 232', plug, 20 sx. of cement through drill pipe, mud up to 40', plug, 1/2 sack of hulls, 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1960
CONSERVATION DIVISION
Wichita, Kansas
03-02-1960

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Triangle Drilling, Inc.
Address Box 287 Russell, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
Donald D. Vaughan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald D. Vaughan
Box 619 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th. day of February, 19 60

My commission expires May 11, 1963

Donna Lea Foelgner
Donna Lea Foelgner, Notary Public.



WELL LOG

OPERATOR A. F. Schmidt
 CONTRACTOR Triangle Drilling, Inc.
 FARM #1 Mermis "C"
 LOCATION SE NW NW of Section 4-13-15W
 Ellis County, Kansas
 ELEVATION 1835 KB
 SURFACE PIPE 8 5/8" cemented @ 232° w/145 sacks common cement
 PRODUCTION D & A
 COMMENCED 2-16-60
 COMPLETED 2-26-60

<u>FORMATION</u>	<u>DEPTH</u>
Surface clay & post rock	75
Shale	250
Shale and sand	355
Sand	392
Hard sand	495
Shale and sand streaks	562
Red bed	918
Anhydrite	956
Shale and shells	1575
Limestone and shale	1720
Broken limestone	1995
Limestone and shale	2746
Limestone	3002
Shale	3017
Limestone	3292
Chert Conglomerate	3310


FORMATION TOPS

Anhydrite	918 (✓ 917)
Topeka	2746 (- 911)
Heebner	2966 (-1131)
Toronto	2986 (-1151)
Lansing	3017 (-1182)
Chert Conglomerate	3292 (-1457)
RTD	3310 (-1475)

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON, SS.

I, Donald D. Vaughan, of the TRIANGLE DRILLING, INC., being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.


 Donald D. Vaughan

Subscribed and sworn to before me this 29th day of February, 1960.


 Donna Lea Foelgner
 Notary Public

My commission expires: May 11, 1963.