

#4

API NUMBER 15-1067-00100-00-01

LEASE NAME Dumler

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
 SW SW SW

SEC. 5 TWP. 13S RGE. 15W (E) or (W)

COUNTY Russell

Date Well Completed

Plugging Commenced 5-18-93

Plugging Completed 5-20-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR V. Francis Weigel Family Partnership

ADDRESS P.O. Box 219 Gorham, Kansas 67460-0219

PHONE# (913) 637-5383 OPERATORS LICENSE NO. 6772

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3293'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	205'	none
				4-1/2"	3290'	2303'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 2870' and 4 sacks cement. Shot pipe loose @2303', pulled up to 1610' and pumped 35 sacks cement, pumped 25 sacks cement @930', 60 sacks cement @470', 20 sacks @205', pulled rest of pipe and capped well off with 10 sacks cement, 60/40 pos, 8% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: V. Francis Weigel Family Partnership

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS.

SUBSCRIBED AND SWORN TO before me this 28th day of May, 1993

Dennis Hammel
 Notary Public

My Commission Expires:



RECEIVED
 STATE CORPORATION COMMISSION
 JUN 1 1993
 06 DI-1993
 CONSERVATION DIVISION
 Wichita, Kansas
 Form CP-4
 Revised 05-88