

15-167-04300-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Russell County. Sec. 35 Twp. 13 Rge. 14 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NW NE NE

Lease Owner Stearns Petroleum, Inc.

Lease Name Mollie Fritzler Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 10 19 49

Application for plugging filed November 10 19 49

Application for plugging approved November 10 19 49


Plugging commenced November 10 19 49

Plugging completed November 18 19 49

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Petty, Hays, Kansas

Producing formation Depth to top 3270 Bottom Total Depth of Well 3270 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				207		
				10-3/4	207	none
				7	3261	2466

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Iane Wells plug set at 3215 ft.
1 sack of Cal-seal set on top of Iane Wells plug
Mud to 2960 feet.
6 sax cement with dump bailer at 2960 feet.
Mud to 200 feet.
Wood plug and rock bridge at 200 feet.
20 sacks of cement on top of bridge
Mud to 35 feet.
Wood plug and rock bridge at 35 feet
15 sacks of cement on top of bridge.

11-23-1949
STEARNS PETROLEUM, INC.
RUSSELL, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Stearns Petroleum, Inc.,
Address Russell, Kansas.


STATE OF KANSAS, COUNTY OF RUSSELL, ss.
O. G. Stearns (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Russell, Kansas.

(Address) November 19 49

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 49



[Signature]

Notary Public.

PLUGGING
FILE SEC 25 T 13 R 14
BOOK PAGE 125 LINE 47

Contractor: Stearns Petroleum, Inc.
Commenced: September 13, 1949
Completed: September 29, 1949

Location: N/2 NE/4, Sec. 35, T 13, R 14,
Russell County, Kansas

Elevation: 1809' D. P.

Casing Record

10-3/4" casing 207' with 140 sx. cement.
7 casing 3260' with 65 sx. cement

Totals

15 min.	160-167
15 min.	380
15 min.	566
15 min.	776
30 min.	1047
20 min.	1202
00	1387
50 min.	1570
30 min.	1634
50 min.	1726
50 min.	2210
55 min.	2735

WELL LOG

	<u>From</u>	<u>To</u>
surface	0	15
shale and shells	15	175
shale	175	207
shale and shells, sand and iron	207	530
shale and red bed	530	810
shale	810	817
lime <u>Anhydrite</u>	817	851
shale and shells	1235 ⁸⁵¹	1235
salt	1235	1420
lime and shale	1420	2815
lime	2815	2914
shale <u>Heebner</u>	2914	2917
lime	2917	3264
<u>Total Depth</u>		3264

STATE OF KANSAS)
(SS
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

SUBSCRIBED and sworn before me this 29 day of Nov 1949

[Signature]
NOTARY PUBLIC

My Commission Expires: Aug 17-1950



NOV 30 1949
11-30-1949

Contractor: Stearns Petroleum, Inc.
Commenced: September 13, 1949
Completed: September 29, 1949

Location: N/2 NE/4, Sec. 35, T 13, R 14,
Russell County, Kansas

Elevation: 1809' D. F.

Casing Record

Totals

10-3/4" casing 207' with 140 sx. cement.
7 casing 3260' with 65 sx. cement

15 min.	160-167
15 min.	380
15 min.	566
15 min.	776
30 min.	1047
20 min.	1202
00	1387
50 min.	1570
30 min.	1634
50 min.	1726
50 min.	2210
55 min.	2735

WELL LOG

	<u>From</u>	<u>To</u>
surface	0	15
shale and shells	15	175
shale	175	207
shale and shells, sand and iron	207	530
shale and red bed	530	810
shale	810	817
lime <u>Anhydrite</u>	817	851
shale and shells	1235 ⁸⁵¹	1235
salt	1235	1420
lime and shale	1420	2815
lime	2815	2914
shale <u>Heebner</u>	2914	2917
lime	2917	3264
<u>Total Depth</u>		3264

STATE OF KANSAS)
(SS
COUNTY OF RUSSELL)

I hereby certify that the above information is true
and correct to the best of my knowledge.

RECEIVED
Conservation Div.
NOV 23 1949
11-23-1949
COMMISSION
KANSAS

SUBSCRIBED and sworn before me this 31st day of Nov. 1949

B. F. Stearns
NOTARY PUBLIC

My Commission Expires: August 17-1950



PLUGGING
FILE SEC 35 T 13 R 14
BOOK PAGE 185 LINE 42