

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Merl Short of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: Jay Hutchison Oil Operations

Complete Address: 7th & Main Streets, Russell, Kansas 67665

Lease Name: Dumler Well No. 1

Location: SE NW SW Sec. 23 Twp. 13 Rgd. 14 (E) (W)

County: Russell Total Depth: 3336'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Short was instructed to plug the well as follows:

8 5/8"-260' s.p. cuc. w/175 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate with 10 sacks of cement in rat hole.

Very truly yours,

*Robert J. Schell*  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
01-18-1982  
JAN 18 1982

CONSERVATION DIVISION  
WICHITA, KANSAS