



15-1107-21733-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

June 20, 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bob Delaney of Rains & Williamson Oil Co has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Company, Inc.

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name: Speere Well No. 1

Location: NE NW NE Sec. 23 Twp. 13 Rge. 14 ~~(E)~~ (W)

County: Russell Total Depth: 3278'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Delaney was instructed to plug the well as follows:

8-5/8"-250'-150 sacks 60/40 Pozmix w/2% gel and 3% cal. chl.

Circulate hole and fill with mud. Pump 50 sacks cement through drill

pipe at 620'. Pump 30 sacks cement through drill pipe at 260'. Fill

hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole

with 10 sacks cement. Cement rathole with 10 sacks cement.

Elev. 1816 GL

Very truly yours,

Phillip R. Dick  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

JUN 23 1981  
06-23-1981  
CONSERVATION DIVISION  
Wichita, Kansas