



GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

15-1167-00100-00-00
State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS
JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION
08-19-1959
AUG 19 1959
CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date August 10, 19 59, authorized the following plugging operation:

Operator's Full Name: R. P. Nixon

Complete Address: 754 E. Wichita St., Russell, Kansas

Lease Name: Dumler Well No. 1

Location: SW-SW-SW Sec. 5 Twp. 13 Rge. 15 (E) (W) X

County: Russell Total Depth: 3400

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 310' with heavy mud.
Set solid rock bridge from 310' to 300' and cement with 30 sacks
thru drill pipe. Fill hole to 40' with heavy mud--set solid bridge
and cap with 10 sacks. Fill, bridge, and cement rathole with 2 sacks.

Very truly yours,

Signed: Walter J. Lawrence
Conservation Division Agent