

APR 18 2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
Wichita, Kansas

LEASE NAME Herl

WELL NUMBER 1

4,900 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 12 TWP. 13 RGE. 22 (E) or (W)

COUNTY Trego

Date Well Completed 11/23/92

Plugging Commenced 3/31/00

Plugging Completed 3/31/00

LEASE OPERATOR Diehl Oil, Inc.

ADDRESS P. O. Box 234 Hays, KS 67601

PHONE#(785) 625-6711 OPERATORS LICENSE NO. 09346

Character of Well oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 3/30/00 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Marmaton-Conglomerate Depth to Top 3950 Bottom 4011 T.D. 4012

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	213	8-5/8"	213'	-0-
		0	4040	5 1/2"	4040'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump 35 sacks SMD cement with 300# hulls followed by 13 sacks gel w/200# hulls followed by 85 sacks SMD cement. 700# psi max pressure, shut in @ 300# psi. Fill up casing with 20 sacks SMD cement. Cement 6' from surface. Cement from 0-2160, gel 2160-3700, cement 3700-4012.

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P. O. Box 466 Ness City, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Glenn D. Diehl

STATE OF Kansas COUNTY OF Ellis, ss.

Glenn D. Diehl, president, (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed thereon are true and correct, so help me God.

(Signature) [Signature]
(Address) P. O. Box 234 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 11th day of April, 19 2000

LORI J. HOVERSON
NOTARY PUBLIC
STATE OF KANSAS

[Signature]
Notary Public

USE ONLY ONE SIDE OF EACH FORM