

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-23462
API NUMBER Docket E-26201

LEASE NAME Simpson D

WELL NUMBER 4

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 9 TWP. 11s RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 7-83

Plugging Commenced 3-19-96

Plugging Completed 3-19-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558, Garden City, Kansas 67846

PHONE# (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well WIW

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-96 KSCC, Hays, Kansas (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Conglomerate Depth to Top 3324 Bottom 3371 T.D. 3408

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	208	8-5/8	208	0
		0	3408	4-1/2	3408	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Ran 2-3/8 tbg to 1052'. Pump 25 sx 60-40 poz 8% gel w/ 1/2# flake. Pull tbg up to 639'. Pump 90 sx 60-40 poz 8% gel. Mix 350# hulls in 25 sx 60-40 poz 8% gel. Pull tbg out. Hook up to 4-1/2 csg. Pump 10 sx 60-40 poz 8% gel w/ 50# hulls. Close well in. Well full of cmt from surface to 1052'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Ken Jehlik

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements and operations herein contained and the log of the above-described well as filed t the STATE CORPORATION COMMISSION are true and correct, so help me God.

(Signature) Ken Jehlik

(Address) _____

NOTARY PUBLIC
Judy R. Schmeier
Notary Public

RECEIVED
APR 03 1996
04-03-96
CONSERVATION SUBSCRIPTION
WICHITA, KS

2nd day of April, 1996

My Commission Expires: August 15, 1996