

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30129
Name: Eagle Creek Corp.
Address 1: 150 N. Main Stc. 905
Address 2: _____
City: Wichita State: KS Zip: 67202
Contact Person: Dave Callewaert
Phone: (316) 264 8044
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 119-20898-00-00
Spot Description: _____
NE SW NW Sec. 29 Twp. 34 S. R. 28 East West
1650 3549 Feet from South Line of Section
990 4301 Feet from East Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW BE SW
County: Meade
Lease Name: Easterday Well #: 2-29
Date Well Completed: _____
The plugging proposal was approved on: 8-24-10 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 8-25-10
Plugging Completed: 8-26-10

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Puffed Out
			8 5/8	1445	—
			4 1/2	3301	2142

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 100 lb. hulls & 20 sx cmt. to plug perfs from 3113 to 2853. Shot & pull 4 1/2 to 1475. Circ. hole w/mud & mixed 50 sx plug 1475 to 1325 40 sx 550 to 430 10 sx 40 to 0. Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515
Name of Party Responsible for Plugging Fees: EAGLE CREEK CORPORATION
State of KANSAS County: SEDGWICK, ss.
DAVID CALLEWAERT Employee of Operator or Operator on above-described well,
(Print Name)

being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

Mail to: KCC - Conservation Division, 190 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 28 2010
KCC WICHITA