

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD
K.A.R. 82-3-117

OPERATOR: License #: 6131
Name: Drillers & Producers, Inc.
Address 1: P.O. Box 385
Address 2: _____
City: Newton State: Ks Zip: 67114 + _____
Contact Person: Bill Hanson
Phone: (316) 841-0022
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Mississippi Depth to Top: ? Bottom: ? T.D. ?
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 115-30111-00-00
Spot Description: _____
NE NE SW SW Sec. 5 Twp. 22 S. R. 4 East West
1,086 Feet from North / South Line of Section
4,081 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Marion
Lease Name: Lathrop-Hawk A Well #: 4
Date Well Completed: Aug 31 1966
The plugging proposal was approved on: July 15 2010 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 9-8-10
Plugging Completed: 9-8-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	oil, water	Surface	8 5/8"	200+	0
		Casing	4 1/2"	2349'	1000'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2297' circulated water to surface then switched to 35 sks 60/40 poz-mix +4%cc +4% gel-Tagged cement at 1984' with wire line-Shot off 1000' of casing-Ran tubing to 272' mixed 142 sks 60/40 poz-mix +4% gel-circulated to surface-pulled tubing and topped off

Plugging Contractor License #: 5870 Name: Phillips Well Services
Address 1: P.O. Box 1263 Address 2: _____
City: El Dorado State: Ks Zip: 67042 + _____
Phone: (316) 321-6650
Name of Party Responsible for Plugging Fees: Drillers & Producers Inc.
State of Ks County, Harvey, ss.
Bill Hanson (Print Name) Employee of Operator or Operator on above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me Gpd.

Signature: Bill Hanson

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

SEP 28 2010

 KCC WICHITA