

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23074-00-00  
Spot: W2SWSW Sec/Twnshp/Rge: 23-13S-14W  
660 feet from S Section Line, 330 feet from W Section Line  
Lease/Unit Name: BRANDENBURG Well Number: 1  
County: RUSSELL Total Vertical Depth: 3325 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 804, LB 30  
DALLAS, TX 75205

Conductor Pipe: Size feet: 8 108.06  
Surface Casing: Size 8.625 feet: 842 350 SX CMT  
Production: Size 5.5 feet: 3324 200 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/22/2002 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-2169

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/22/2002 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2976' and dumped 5 sxs cement.  
Shot off casing at 1953'.  
Pulled to 1400' and loaded hole with 10 sxs gel with 400# hulls.  
Pumped 100 sxs 60/40 pozmix - 10% gel cement with 400# hulls.  
Pulled to 850' and mixed 7 sxs gel with 200# hulls.  
Pumped 60 sxs cement with 100# hulls.  
Pulled to 200' and circulated with 40 sxs cement with 100# hulls.

RECEIVED  
11-27-2002  
NOV 27 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Case Morris  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 11-27-02

INV. NO. 2003060870

NOV 26 2002

STATE: KANSAS COUNTY: RUSSELL 23-13S-14W  
FIELD: RUSSELL W2 SW SW  
OPER: MAI OIL OPERATIONS 660 FSL 330 FWL SEC  
WELL: 1 BRANDENBURG WELL CLASS: DO ELEV: 1845 KB  
API: 15-167-23074 STATUS: OIL 1840 GR  
SPUD: 10/22/93 COMP: 03/28/94  
DTD: 3325 LTD: FTD: ARBUCKLE PBDT:

LOC: WITHIN CITY LIMITS RUSSELL, KS

IP: COMP 3/28/94, IPP 10 BO, 5 BWPD PROD ZONE- ARBUCKLE 3269-3282(GROSS)  
NO CORES OR DSTS

LOG TOPS:

TARKIO	2348 -503	LANSING-KANSAS CITY	2987 -1142
TOPEKA	2702 -857	B/ KANSAS CITY	3244 -1399
HEEBNER	2928 -1083	ARBUCKLE	3266 -1421
TORONTO	2948 -1103		
TD	3325 -1480		

LOG TYPES: CNDL, DILL, DL, GR, MINL;

CSGS: 8 5/8 @ 842 W/350 SX, 5 1/2 @ 3324 W/200 SX; TBG: 2 7/8 @ 3283; RIG REL  
11/02/93

PERFS: PERF (ARBUCKLE) 3302-3303 W/4 PF, ACID W/250 GALS, , SQZD OFF PERF  
(ARBUCKLE) 3289-3291 W/6 PF, ACID W/250 GALS, , SQZD OFF

(OVER)