

6 070638

2-24-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 167-22,287--00-00

C. SW SW, SEC. 24, T 13 S, R 14 (W) #
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6650

Lease Name Krug C Well # 2

Operator: Jay Hutchinson Oil

County Russell 111.15

Name & Address Box 872

Well Total Depth 3420 feet

Russell, Kansas 67665

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling and Allied, license Number _____

Address Box 768, Great Bend, Ks. and Box 31, Russell, Ks. 67665

Company to plug at: Hour: 11:00 AM Day: 24 Month: Feb Year: 19 88

Plugging proposal received from Gary Burk

(company name) Great Bend Casing Pulling (phone) 316-793-9721

were: 8 5/8" - 261' S.P. cwc w/170 sks; 4 1/2" csg set at 3340' w/NA, at bottom sand to 3100' and w/4 sks cement; Shot casing 3 times, recovered 2,096'. Proposal 150 sks 65/35 Pozmix 10% Gel and 5 sks Hulls. Pump in 8 5/8" S.P. with pump truck pump in 25 sks cement followed with another 125 sks cement with Hulls added. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 Noon Day: 24 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Ordered 150 sks 65/35 Pozmix 10% Gel and 5 sks Hulls. Pumped in 8 5/8" S.P. with pump truck. Pumped in 25 sks cement followed with another 125 sks cement with 5 sks Hulls added in. Max Psig. 700. Shut in at 600 Psig. Cemented by Allied Cementing.

RECEIVED STATE CORPORATION COMMISSION

Remarks: 03-16-1988 (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging. CONSERVATION DIVISION Wichita, Kansas

Signed Marion J. Schmidt (TECHNICIAN)

DATE 3-16-88 INV. NO. 20128