

15-167-21142-00-00

To: 6 070644  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 4-19-78  
NE NE NW SEC. 35, T 13 S, R 14 W/E  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6650  
Operator: Jay Hutchinson Oil  
Name & Address: Box 872  
Russell, Ks. 67665

Lease Name Murphy Well # 2  
County Russell 115.05  
Well Total Depth 3540 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing and Allied Cmt. License Number \_\_\_\_\_

Address Box 768 Great Bend, Ks. and Box 31, Russell, Ks. 67665

Company to plug at: Hour: 4:20 PM Day: 24th Month: Feb. Year: 19 88

Plugging proposal received from Gary Burk

(company name) Great Bend Casing Pulling (phone) 316-793-9721

were: 8 5/8" 271' S.P. cwc w/NA 4 1/2" csg set at 3505' w/NA. Perfs at 3440' to 3529'.

No csg recovery. Tubing stuck in hole at 430'. Ran interial tubing inside 2 7/8" washed down to 1150'; Proposal, perforate at 980' and 377'. Order 300 sks cement (50 sks Common) 250 sks 65/35 Pozmix 10% Gel. Load and squeeze below bridge and above bridge with cement, annulus open. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:20 PM Day: 24th Month: Feb. Year: 19 88

ACTUAL PLUGGING REPORT Ordered 50 sks Class A Cement and 250 sks ATL 65/35 Poz

10% Gel. Pump in with pump truck. Shot csg at 980'. Pumped through tubing 50 sks of Class A Cement and 100 sks of ATL Cement. Shut in at 250 Psig. Then, shot tubing at 377' and circulated 15 sks cement to surface. Squeezed 4 1/2" csg with 135 sks cmt. Cement circulated out of annulus. Max pressure 700 Psig. Shut in at 600 Psig. Total cement  
Cement. RECEIVED. By Allied STATE CORPORATION COMMISSION 03-17-1988

Remarks: (If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Marion J. Schmidt (TECHNICIAN) CONSERVATION DIVISION Wichita, Kansas

INVOICED  
DATE 3-31-88  
INV. NO. 20143