

4-041460

5-20

15-167-00100-00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- 2-4-80 OWWO

SW SW SW /4 SEC. 05, 13 S, 15 W
330 feet from S section line
4950 feet from E section line

Operator license# 6772 Lease Dumler (OWWO) well # 1

Operator: V. Francis Weigel County Russell

Address: P.O. Box 219 Well total depth 3290 feet ^{106.92}
Gorham, Kansas 67640-0219 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 205 feet
w/175 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing - Allied Cementing License#

Address: Chase, Kansas - Russell, Kansas

Company to plug at: Hour: 9:00A.M. Day: 20 Month: May Year: 93

Plugging proposal received from: David Brady

Company: Kelso Casing Phone:

Were: 4 1/2" casing set @ 3290' w/225 sx. cement. Perf. @ 2920' -
3034'. Salt @ 1610'. Anhy. @ 930'. Dakota @ 470'.
Other: recovered 2300' of 4 1/2" casing. Plug bottom with sand to
2870' and 4 sx. cement. Ordered 150 sx. 60/40 pozmix - 8% gel. with
1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 20, Month: May, Year: 93

Actual plugging report:
Spot 35 sx. @ 1610'.
Spot 25 sx. @ 930' with 200# hulls.
Spot 60 sx. @ 470' with 100# hulls.
Spot 20 sx. @ 205'.
Spot 10 sx. at surface.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation:

I did[X] / did not[] observe the plugging.

INVOICED

DATE 6-15-93

BY 37915

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 1993
(agent) Dennis L. Hamel
06-09-1993
Form CP-20
CONSERVATION DIVISION
Wichita, Kansas