

2-17-88 12-20-77

6 070632

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-1167-2114-00-00

SE NE NW, SEC. 35, T 13 S, R 14 W/E
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6650

Operator: Jay Hutchinson
Name & Address: Box 872
Russell, Kansas 67665

Lease Name Murphy Well # 1

County Russell 106.34
Well Total Depth 3272 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing and Allied Cmp License Number

Address Box 768 Great Bend, Kansas 67530 Box 31, Russell, Kansas 67665

Company to plug at: Hour: 9:00 AM Day: 17 Month: Feb Year: 19 88

Plugging proposal received from Rich McIntyre and Gary Beck

(company name) Great Bend Casing Pulling (phone) 913-483-4006

were: 8 5/8" - 248' S. P. cwc w/N. A.; 5 1/2" csg set at 3270' w/75 sks cement.

Perfs at 2940' to 3208'; at bottom sand to 2890' and w/5 sks cement. Shot and

recovered 1850' of 5 1/2" csg; Shot at 2023' and 1795'; Proposal 150 sks (ATL)

65/35 Pozmix 10% Gel and 5 sks Hulls; Pump in 8 5/8" csg with pump truck; Pump in

25 sks cement followed with 125 sks cement w/5 sks added in. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 PM Day: 17 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Ordered 150 sks (ATL) 65/35 Pozmix 10% Gel and 5 sks Hulls pumped

in with pump truck. Pumped in 8 5/8" S.P. 25 sks cement followed with 125 sks cement

w/5 sks Hulls added in. Max pressure 450 Psig; Shut in at 250 Psig. Cemented by

Allied Cementing.

STATE CORPORATION COMMISSION

MAR - 2 1988
03-02-1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: 2-23-88
(If additional description is necessary, use BACK of this form.)

I (did not observe) observe this plugging.

INVOICED

Signed Marion J. Schmidt (TECHNICIAN)

DATE 3-2-88

INV. NO. 19962