

Tip: 6 070634
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-17-88
API NUMBER 15-167-21512-00-00
C NW SW, SEC. 35, T 13 S, R 14 (W) W
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6650

Operator: Jay Hutchinson
Name & Address: Box 872
Russell, Kansas 67665

Lease Name Mai Well # 1
County Russell 106.99
Well Total Depth 3292 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Csg and Allied Cmt. License Number _____

Address Box 768 Great Bend, Ks. 67530 and Box 31 Russell, Ks. 67665

Company to plug at: Hour: 12:30 PM Day: 17 Month: Feb Year: 19 88

Plugging proposal received from Rich McIntyre and Gary Beck

(company name) Great Bend Casing Pulling (phone) 913-483-4006

were: 8 5/8" - 247' S.P. cwc w/N.A. ; 5 1/2" csg set at 3289' w/N.A.

Perfs at 2960' to 3168' - 3192'; Sand to 2900' and with 5 w/sks cmt. Shot csg at 1800' and

1742'. Recovered 1745' of 5 1/2" csg; Proposal 150 sks (A.T.L.) 65/35 Pozmix 10% Gel and

5 sks Hulls. Pump in 8 5/8" with pump truck pump in 25 sks cmt followed with 125 sks

cmt w/Hulls added in. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 PM Day: 17 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Ordered 150 sks (A.T.L.) 65/35 Pozmix 10% Gel and 5 sks Hulls.

with pump truck pump into 8 5/8" S.P. Pump in 25 sks cement, followed with 125 sks cement

with 5 sks Hulls added in. Max pressure 600 Psig; Shut in at 200 Psig. Cemented by

Allied Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

MAR - 2 1988
03-02-1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: 2-23-88

(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 3-2-88

INV. NO. 19964

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt