

6 062115

3-26

182 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-21443-00-00

NE, SEC. 35, T. 13 S, R. 14 W/E

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6284

Operator: Vonfeldt Oil Oper Inc.

Name & Address: Box 611

Russell, Ks. 67665

Lease Name Dumler Well # 1

County Russell 105.95

Well Total Depth 3260 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635

Address Box 611 Russell, Ks. 67665

Company to plug at: Hour: 9:00 AM Day: 26 Month: Mar Year: 19 90

Plugging proposal received from Roy Vonfeldt Vonfeldt Oil Oper Inc.

(company name) Vonfeldt Oil Oper Inc. (phone) 913-483-6446

were: Order 300 sks 60/40 poz 8% gel 5 sks hulls.

D.V. from 850' to surface.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 AM Day: 26 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" set at 258' w/cwc. 4 1/2" set at 3257' w/125 sks.

Top perf at 2985'. Plugged bottom w/sand and 5 sks cement to 2925'.

Shot pipe one time and recovered 0'. Pumped in 4 1/2" 25 sks cement followed w/5 sks hulls in 175 sks cement w/900 psi. 8 5/8" cement to surface.

Remarks: By Allied Shot hole in casing at 975'. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-9-90 04-02-1990

INV. NO. 27820

Signed Gilbert G. Scheck (TECHNICIAN)

Gilbert G. Scheck