

To: 6 070630  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-16-88  
API NUMBER 15-167-22090-00-00  
NE SE 9W SEC. 23, T 13 S, R 15 W/E  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6650  
Operator: Jay Hutchinson  
Name & Address: Box 872  
Russell, Kansas 67665

Lease Name Dockendorp Well # 1  
County Russell 107.97  
Well Total Depth 3322 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing and Allied Cement License Number \_\_\_\_\_

Address Box 768 Great Bend, Ks. 67530 and Box 31, Russell, Ks. 67665

Company to plug at: Hour: 10:00 AM Day: 16 Month: Feb Year: 19 88

Plugging proposal received from Rich McIntyre and Gary Beck

(company name) Great Bend Casing Plugging (phone) 913-483-4006

were: 8 5/8" - 250' S.P. cwc w/150 sks. 5 1/2" csg set at 3319' w/125 sks cmt.

Perfs at 3303' - 07' at bottom sand csg to 3048' and w/5 sks cmt. Shot csg twice;

Recovered 1910' of 5 1/2" csg. Proposal 150 sks 65/35 Pozmix 10% Gel and 5 sks Hulls.

Pump in 8 5/8" csg with pump truck; pump in 25 sks cement, then, 125 sks cement

with Hulls added, shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: Noon Day: 16 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Ordered 150 sks (ATL) 65/35 Pozmix 10% Gel and 5 sks Hulls.

Pumped into 8 5/8" csg with pump truck. Pumped in 25 sks cmt followed with another 125

sks cement with 5 sks Hulls added in.

Max Psig. 500 - Shut in at 300 Psig.

Cemented by Allied Cementing.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR - 2 1988  
03-02-1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: 2-23-88  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 3-2-88  
REV. NO. 19963  
observe this plugging.

Signed Marion J. Schmidt  
(TECHNICIAN)  
Marion J. Schmidt LR