

15-167-20417-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Russell County, Sec. 15 Twp. 13S Rge. (E) 15 (W)  
Location as "NE/CNWxSWx" or footage from lines NE NW NE  
Lease Owner Clinton Oil Company  
Lease Name Edmund J. Dinkel Well No. 1-V  
Office Address 217 North Water Street, Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 9, 1970  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced May 9, 1970  
Plugging completed May 9, 1970  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott - McPherson, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3327 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	321'	8-5/8"	321'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth to 500 Feet,  
Plug & 50 sax Cement; Heavy Mud to 300  
Feet, Plug & 35 sax Cement; Mud to 40  
Feet, 1/2 sax Halls, Plug Bridged with  
Kelly & 13 sax Cement to Base of Cellar;  
2 sax Cement in Rat Hole. Job Completed  
@ 4:00 P.M. on 5/9/70.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
05-13-1970

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wayne W. Kahmeyer of Sage Drilling ~~(employee of owner or owner or operator)~~ of the above described

~~well~~ being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer  
500 Bitting Building, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 12th day of May, 1970

Louise K. Whitted  
Louise K. Whitted - Notary Public.



My commission expires November 26, 1970.

15-167-20417-00-00

DRILLERS LOG

EDMUND J. DINKEL NO. 1-V

CASING RECORD:	OPERATOR:	Clinton Oil Company	DESCRIPTION:
8-5/8" @ 321'	CONTRACTOR:	Sage Drilling Co., Inc.	NE NW NE
w/200 sax cement	COMMENCED:	April 30, 1970	Sec. 15-13S-15W
TOTAL DEPTH:	COMPLETED:	May 9, 1970	Russell Co., Kansas
3327'			ELEVATION: 1845 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Rock	0	850	
Red Bed & Shale	850	910	
Anhydrite	910	943	
Shale & Sand	943	1531	
Shale	1531	1570	
Lime & Shale	1570	2185	
Shale & Lime	2185	2380	
Lime & Shale	2380	2575	
Shale & Lime	2575	2700	
Lime	2700	2771	
Lime & Shale	2771	2856	
Lime	2856	3075	
Lime & Shale	3075	3123	
Lime	3123	3200	
Lime & Shale	3200	3213	
Lime & Chert	3213	3257	
Lime, Shale & Chert	3257	3290	
Lime & Dolomite	3290	3327	D&A


RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
05-13-1970

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Wayne W. Kahmeyer  
Wayne W. Kahmeyer

Subscribed and sworn to before me this 12th day of May, 1970.



Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.