

15-167-00~~469~~⁶⁴⁹-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County, Sec. 16 Twp. 13 Rge. 15 (E) W (W)
Location as "NE/CNW/SW" or footage from lines E/2 SW NW
Lease Owner Solar Oil Company
Lease Name Deines Well No. 1 **AWS KCC**
Office Address 1117 Union National Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 26 1963
Application for plugging filed June 26 1963
Application for plugging approved June 26 (verbally) 1963
Plugging commenced June 26 1963
Plugging completed June 26 1963
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3296 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	902'	8 5/8"	902'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole from total depth to 350' with heavy mud, with a plug and 25 sacks of cement at this point. Heavy mud to 40' with a plug and 10 sacks of cement at this point; 2 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1963
07-16-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Harms Drilling Company
Address Box 488 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms
Box 488 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1963

My commission expires January 22, 1966.

Helen E. Gearhart
Helen E. Gearhart
Notary Public.

15-167-00649-00-00

D R I L L E R S L O G

COMPANY: SOLAR OIL COMPANY
FARM: DEINES #1
COMMENCED: June 17, 1963

E/2 SW NW Section 16-13-15W
RUSSELL COUNTY, KANSAS
COMPLETED: June 26, 1963

ELEVATION: 1845

0 - 40	Post lime
40 - 220	shale-hard sand
220 - 350	sand & shale
350 - 358	hard sand
358 - 395	sand & shale
395 - 660	sand
660 - 800	hard sand, red bed and pyrite
800 - 892	red bed
892 - 935	Anhydrite
935 - 1450	red bed & shale
1450 - 1740	shale-lime
1740 - 2835	lime-shale
2835 - 2965	lime
2965 - 2968	Heebner
2968 - 3269	lime
3269 - 3282	Conglomerate
3282 - 3296	Arbuckle
3296	Total depth

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1963
07-16-1963
CONSERVATION DIVISION
Wichita, Kansas

SET 902' of 8 5/8" surface pipe. Cemented with 400 sacks of cement with 2% gel and 2% calcium chloride.

TOPS: ANHYDRITE - 892
TARKIO - 2449
HEEBNER - 2965
LANSING - 3013
CONGLOMERATE - 3269
ARBUCKLE - 3282

DRY, plugged, and abandoned.

A F F I D A V I T

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, Allan Harms of the Harms Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms
Allan Harms

Subscribed and sworn to before me this 8th day of July, 1963.

Helen E. Gearhart
Helen E. Gearhart Notary Public

My commission expires: January 22, 1966.

