


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Russell County. Sec. 23 Twp. 13 Rge. 15 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE/SW/SE/4  
Lease Owner Earl F. Wakefield  
Lease Name Wakefield- Olson Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced April 26 19 61  
Plugging completed May 9 19 61  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3327 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3327 feet to surface, feet for each plug set.  
Pipe set at 3324-no perforations. Hole filled with sand to 3315; five sacks of cement placed in bottom of hole with dump bailer. All pipe pulled from hole; hole filled with mud to 300 feet; ten foot rock bridge installed between 300 and 290 ft; hole then filled to bottom of cellar with concrete.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 7 1961  
06-07-1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and sons Pipe Pulling co  
Address Russell, Kansas.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
EARL F. WAKEFIELD (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield  
515 UNION CENTER BLDG, WICHITA  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of JUNE, 19 61

Wanda W. Riley  
WANDA W. RILEY Notary Public.

My commission expires JANUARY 25, 1965



15-167-00210-20-00

LEASE: August Olson #1  
OPERATOR: Earl F. Wakefield  
CONTRACTOR: Earl F. Wakefield  
COMM: 6/27/58 COMP: 7/4/58

LOCATION: SE SW SE  
23-13S-15W  
Russell County, Kans.  
CASING: 8 5/8" Set @ 691  
5 1/2" Set @ 3324

RECEIVED  
STATE CORPORATION COMMISSION

ELEVATION: 1892 G.L.  
1895 D.F.  
1898 K.B.

JUN 7 1961  
06-07-1961  
CONSERVATION DIVISION  
Wichita, Kansas

Soil and Shale	30
Shale and Lime Streaks	240
Pyrite	248
Shale and Sand	435
Sand and Pyrite	490
Shale	630
Red Rock	950
Lime	1020
Shale	1350
Shale and Pyrite	1450
Shale and Lime Streaks	1630
Anhydrite and Shale	1720
Lime	2140
Lime and Shale	2405
Shale	2420
Shale and Lime	2495
Shale	2535
Lime and Shale	2731
Lime	2777
Lime and Shale	2789
Lime	2910
Lime and Shale Streaks	2999
Lime	3014
Heebner Shale	3018
Lime and Shale	3066
Lans. K.C. Lime	3075
Lime	3198
Lime and Shale Streaks	3215
Lime	3323
Arbuckle	3326

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the August Olson #1 well, located SE SW SE Section 23-13S-15W Russell County, Kansas.

Earl F. Wakefield  
Earl F. Wakefield

Subscribed and sworn before me this 10 day of July, 1958.

C. A. Snow  
C. A. Snow Notary Public

My commission expires July 26, 1958.