


STATE OF KANSAS  
 STATE CORPORATION COMMISSION

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 800 Bitting Building  
 Wichita, Kansas

OR  
**FORMATION PLUGGING RECORD**

Strike out upper line  
 when reporting plug-  
 ging off formations.

Russell County. Sec. 23 Twp. 13 Rge. 15 (E).....(W)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW NW NW  
 Lease Owner. Cyrus N. Peterson et al  
 Lease Name. E. M. Cook Well No. 1  
 Office Address. Russell, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed. May 19 1950  
 Application for plugging filed. May 20 1950  
 Application for plugging approved. May 20 1950  
 Plugging commenced. May 20 1950  
 Plugging completed. May 21 1950  
 Reason for abandonment of well or producing formation. Dry Hole



Locate well correctly on above  
 Section Plat

If a producing well is abandoned, date of last production.....19.....  
 Was permission obtained from the Conservation Division or its agents before plugging was com-  
 menced? Yes

Name of Conservation Agent who supervised plugging of this well. Eldon Petty, Hays, Kansas  
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3321 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	271	None
				Cemented top to bottom		
				5 1/2"	3303	2550
				Cemented w/150 sacks cement		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Hole filled with chat from 3321 to 3300feet  
 Plug and bridge set at 3300 feet  
 4 sacks cement placed on top of bridge at 3300 feet  
 Hole filled with rotary mud to 270 feet  
 Plug and bridge set at 270 feet  
 15 sacks cement placed on top of bridge at 270 feet  
 Hole filled with rotary mud to 35 feet  
 10 sacks of cement on top of plug at 35 feet to top of hole

MAY 27 1950  
 STATE CORPORATION COMMISSION  
 KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. O. G. Stearns  
 Address. Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
O. G. Stearns (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
 described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Russell, Kansas  
 (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of May, 1950

My commission expires

June 20, 1953

**PLUGGING**  
 FILE SEC 23 T 13 R 15 W  
 BOOK PAGE 8 LINE 20

COOK # 1

Company: Stearns Petroleum, Inc.  
 Commencement: 4-30-50  
 Completion: 5-12-50

Location: SW NW NW, Sec. 23, T13, R15,  
 Russell County, Kansas.

Elevation: 1873' D. F.

Casing Record:

8-5/8"-----271'  
 5-1/2"-----3303'

Totco:  
 30 min. 229'  
 45 min. 472'  
 15 min. 643'  
 30 min. 1230'  
 30 min. 1390'  
 15 min. 1980'  
 15 min. 2204'  
 1° 2725'

WELL LOG

shale and shells	0	271
shale and sand	271	340
sand and iron	340	410
shale	410	525
sand and shale	525	690
red bed	690	935
<u>Anhydrite</u>	935	968
red bed	968	1125
shale and shells	1125	1370
salt	1370	1570
shale and shells	1570	1620
shale and lime	1620	2290
shale and shells	2290	2430
shale and lime	2430	2880
lime	2880	2925
lime and shale	2925	2986
<u>Heebner</u>	2986	
lime and shale	2986	3039
lime <u>Top of Kansas City</u>	3039	
lime	3039	3302
<u>Arbuckle</u>	3302	
R. T. D.	3305	

1873  
 1950  
 RING  
 MAY 27 1950  
 05-27-1950  
 NOTARY PUBLIC  
 KANSAS


STATE OF KANSAS )  
 ) ( SS  
 COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 22nd day of may, 1950.

Harold J. Heebner  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: June 20, 1953



PLUGGING  
 FILE 23-13 (SW)  
 BOOK PAGE 8 LINE 20