

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05088-00-00  
Spot: NWNE Sec/Twnshp/Rge: 10-11S-20W  
330 feet from N Section Line, 990 feet from E Section Line  
Lease Name: YOHE Well #: 5  
County: ELLIS Total Vertical Depth: 3617 feet

Operator License No.: 34147  
Op Name: ACE WELL SERVICE, INC.  
Address: 120 CINDY DR PO BOX 606  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	226	0	w/unknown sxs cmt
PROD	5.5	3617	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2010 2:00 PM  
Plug Co. License No.: 34147 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: SHAWN D. EVANS Company: ACE WELL SERVICE, INC. Phone: (785) 445-2942

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls - 10 sxs gel spacer.  
Perforated at 2000' - 1450' - 1200' - 230'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/24/2010 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3240' - pumped 10 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1990' - pumped 180 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.  
Pulled all tubing. Hooked to 5 1/2" casing - pumped 60 sxs 60/40 pozmix - 4% gel to fill casing and circulate out 8 5/8".

Perfs:

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060013

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 02 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #41781.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

M & L DRILLING

#5 YOHE

10-11-20W  
APP NW NE NE

Contr. LEWIS DRLG

ELLIS County

E 2019RB Comm.

Comp. 9-16-55

IP 402 BOPD

Tops	Depth	Datum
HEEB	3258	-1239
BR LM	3283	-1264
LANS	3294	-1275
CONG	3546	-1527
SIMP	3589	-1570
ARB	3608	-1589
TD	3617	-1598

Casing  
 8" 226 DST 3322-34/1 HR,  
 5" 3617 600' GAS, 120' HOOM  
 180' CL FR OIL, BHP 765#  
 DST 3342-56/1 HR, 240' GAS  
 370' CL FR OIL, BHP 750#  
 DST 3375-85/1 HR, 110' OGM  
 120' FR OIL, 125' SW, BHP  
 1125#: DST 3610-17/1 1/2 HR, 55'  
 OGM, 25' SW, BHP 800#  
 EAGLE CREEK PERF 35/3346-  
 52: 1 BOPH, NATL  
 ACID 2500: 45  
 BOPH, NO WTR:

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS