

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29372-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 19-26S-18E
640 feet from N Section Line, 700 feet from W Section Line
Lease Name: WOLFF Well #: 4-19
County: ALLEN Total Vertical Depth: 1178 feet

Operator License No.: 33583
Op Name: ADMIRAL BAY (USA) INC.
Address: 7060 S TUCSON WAY, STE B
CENTENNIAL, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	35		5 SX CMT.
PROD	4.5	1168		152 SX CMT.

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/26/2010 1:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, LLC Phone: (620) 433-7196

Proposed Plugging Method: Run tubing in well to 1160', spot 50' cement plug, pull tubing to 500', spot 50' cement plug, pull tubing to 200', circulate portland cement to surface.

Plugging Proposal Received By: JOHN ALMOND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/27/2010 12:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran tubing to 1160', spot 50' cement plug, pull tubing to 500', spot 50' cement plug, pull tubing to 200', circulate portland cement to surface, pulled tubing and topped off well.

Perfs:

Top	Bot	Thru	Comments
1045	1048		

RECEIVED
JUN 30 2010 JA
KCC Chanute Dist. #3

INVOICED
DATE 10-14-2010
INV. NO. 2011060014

Remarks:

Plugged through: TBG

District: 03

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 06 2010
CONSERVATION DIVISION
WICHITA, KS

Signed

John Almond
(TECHNICIAN)