

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00785-00-00
Spot: NESWNE Sec/Twnshp/Rge: 6-2S-18W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HUFFSTUTTER A Well #: 5
County: PHILLIPS Total Vertical Depth: 3521 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	180	0	w/unknown sxs cmt
PROD	5.5	3516	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2010 4:00 PM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PRODUCTION Phone: (785) 302-1435

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perforated at 1800' and 230'.

Plugging Proposal Received By: PAT BEDORE WitnessType: NONE
Date/Time Plugging Completed: 05/05/2010 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2700' - pumped 150 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 2000' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1000' - pumped 110 sxs 60/40 pozmix - 4% gel with 100# hulls to circulate to surface.
Hooked to 8 5/8" x 5 1/2" annulus - pumped 50 sxs 60/40 pozmix - 4% gel - cement circulated out the 5 1/2" casing.

Perfs:

Top	Bot	Thru	Comments
3492	3496		
3479	3486		
3455	3462		
3436	3444		

RECEIVED
JUL 08 2010
KCC WICHITA

INVOICED
DATE 10-14-2010
INV. NO. 2011060019

Remarks: ALLIED CEMENTING COMPANY-TICKET #41676.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

B & R DRILLING, INC. #5 HUFFSTUTTER 6-2-18W
 NE SW NE
 Contr. PHILLIPS County
 E 2250 Comm. 8-20-50 Comp. 9-22-50 IP 283 BOPD
 PHY POT

Tops	Depth	Datum
ANH	1795	+455
HEEB	3357	-1167
LANE	3382	-1132
T.D.	3521	-1271

Casing
 8" 180 PERF 35 S, 3479-86
 5" 3516 12 S, 3492-96
 PB 3466
 PERF 24 S, 3455-62
 ACID 3000
 SWB 4 BOPH/6 HRS:
 PB 3447
 PERF 24 S, 3436-44
 SWB 3 BOPH
 ACID 4000
 SWB 8½ BOPH

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS