

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01865-00-01
Spot: W2NWSE Sec/Twnshp/Rge: 1-21S-1W
1852 feet from S Section Line, 2323 feet from E Section Line
Lease Name: GHWFU (BRANT B) Well #: 11 (2)
County: MCPHERSON Total Vertical Depth: 3422 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	206		175 SX
PROD	4.5	3420	300	75 SX

Well Type: OIL UIC Docket No: E13747.6 Date/Time to Plug: 07/01/2010 9:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P. BANDY Company: Phone: (620) 628-4428

Proposed
Plugging
Method:

AS PER KCC

Plugging Proposal Received By: Witness Type: NONE
Date/Time Plugging Completed: 07/01/2010 11:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:

6/28/2010 CYCLONE OUT AND PULLED TUBING, AND DROPPED SAND FOR BOTTOM PLUG. 6/30/2010 CYCLONE TAGGED SAND AND CAPPED W/5 SX @ 3350'. TE PE PERFORATED CASING AT 250' AND CIRCULATED WATER DOWN CASING AND UP BACKSIDE. CYCLONE RIGGED DOWN AND MOVED OFF WELL. 7/1/2010 QUALITY CEMENT OUT AND CIRCULATED 190 SX DOWN CASING AND UP BACKSIDE. THEN TIED ON TO BACKSIDE AND SQUEEZED 20 SX DOWN BACKSIDE. BOTH SIDES HOLD 200 PSI. TK #5010 210 SX 60/40 POS W/4% GEL. 7/2/2010 TOP PLUG DOWN APPROX 100' INSIDE 4.5". TEPE MIXED DRY SX TO TOP OFF WELL. BY THE TIME I GOT TO THE LOCATION WELL HEAD AND PITS WERE FILLED IN.

Perfs:

Top	Bot	Thru	Comments
3392	3404	CSG	

NVOICED
DATE 10-14-2010
INV. NO. 2011060020


RECEIVED
JUL 19 2010
KCC WICHITA

Remarks: PLUGGED DUE TO FAILED MIT.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

✓