

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-30112-00-00  
Spot: SESESW Sec/Twnshp/Rge: 6-21S-1E  
334 feet from S Section Line, 2986 feet from E Section Line  
Lease Name: FAST B Well #: 1  
County: MARION Total Vertical Depth: 3505 feet

Operator License No.: 5920  
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G  
Address: PO BOX 522  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		175 SX CMT
PROD	4.5	3504	300	175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2010 10:00 AM  
Plug Co. License No.: 5920 Plug Co. Name: BANDY, TERRY P. DBA TE-PE OIL & GAS  
Proposal Rcvd. from: TERRY P BANDY Company: \_\_\_\_\_ Phone: (620) 628-4428

Proposed Plugging Method:

AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/25/2010 4:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

6/25/2010 BOTTOM PLUG HAD BEEN SET YEARS AGO WHEN WELL WAS SHUT IN. CYCLONE TAGGED SAND @ 3300' AND CAPPED WITH 5 SX. THEY TIED ON TO CASING TO PULL STRETCH AND CASING PARTED. THEY PULLED OUT APPROX 300' OF CASING. BUD DAVIS OUT TO RUN PLUGGING JOB FOR TERRY BANDY. CYCLONE BAILED FLUID DONE TO 300'. THEY ARE GOING TO DO TOP PLUG WITH SLURRY MIX. BUD ORDERED 6 YDS @ 22SX/YD FROM THE HILLSBORO REDIMIX. SLURRY ARRIVED AT 3:30 PM. I HAD CYCLONE RUN THE BAILER A COUPLE OF MORE TIMES TO MAKE SURE FLUID WAS STAYING @ 300'. THEY DUMPED THE SLURRY. THE HOLE TOOK MOST OF THE 6 YDS. FINISHED @ 4:30 PM. CONCRETE PRODUCTS TK #45711 132 SX CLASS A. 6/28/2010 I CHECKED TOP PLUG DOWN 1'.

Perfs:

Top	Bot	Thru	Comments
3372	3376	CSG	HUNTON


INVOICED  
DATE: 10-14-2010  
INV. NO. 2011060020  
RECEIVED  
JUL 15 2010  
KCC WICHITA

Remarks: 3300' PBTD PLUGGED DUE TO 10 YEAR RULE

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)