

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20579-00-01  
Spot: SENWNW Sec/Twnshp/Rge: 7-11S-15W  
990 feet from N Section Line, 990 feet from W Section Line  
Lease Name: CHRISLER ELLIOTT UNIT Well #: 7  
County: RUSSELL Total Vertical Depth: 3543 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	221	0	200 SX
PROD	4.5	3543	0	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/15/2010 10:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: ROBERT GRANT Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Perf at 500' - 950' - 1600'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/15/2010 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2912' - pumped 125 sxs cement with 200# hulls.  
Pulled tubing to 1750' - pumped 60 sxs cement with 200# hulls - cement circulated.  
POOH. Hooked up to casing and pumped 20 sxs cement at 500#.  
Cement circulated out Braden head.  
S.I.P. 250#.

Perfs:

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060021

Remarks: ALLIED CEMENTING COMPANY-TICKET #44169.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

RECEIVED

JUL 27 2010

Form CP-2/3

KCC WICHITA

JUL 19 2010

GRAHAM-MICHAELIS CORP. "OWWO" 7-11-15W  
 P.O. BOX 247 #1-7 ELLIOTT 1140' FNL&910' FWL,  
 WICHITA, KS 67201 NW/4  
 CONTR REVLIN DRILLING, INC. CTY RUSSELL

GEOL \_\_\_\_\_ FIELD FAIRPORT NW EXT (1/4 NW)

E 1899 KB CM 9/1/81 CARD ISSUED 1/14/82 IP OIL WELL  
 LANS - INTV NA

+	+	+
+	+	+
+	+	+

API 15-187-20,579A

LOG	TOPS	DEPTH	DATUM
ANH		1072	+ 827
B ANH		1107	+ 792
TOP		2804	- 905
HEEB		3049	-1150
TOR		3072	-1173
LANS		3098	-1199
B KC		3347	-1448
ARB		3516	-1617
LTD		3542	-1643

OLD INFO: OPERATOR WAS CLINTON OIL,  
 #1-V M. ALBRECHT, CONTR WAS RED TIGER,  
 GEOLOGIST WAS HARLAN DIXON, SPD 2/  
 26/73, SET 10 3/4" 221/200SX,  
 COMPLETED AS D&A/ARB 3/22/73

DST (1) 3051-3125/1', REC 90' M W/F  
 SP OIL, SIP 919/45"-812#/45",  
 FP 36-81/72-104#  
 DST (2) 3121-3143/50", REC 30' M,  
 SIP 425#/45"-416#/30#, FP 36-45/  
 45-45#  
 DST (3) 3138-3183/90", REC 5' O&GCM,  
 30' M, SIP 104/45#-103#/90", FP  
 36-45/45-54#

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

(OVER)