

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22530-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 3-16S-25W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: REUSSER Well #: 1
County: NESS Total Vertical Depth: 4535 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	337		WITH 250 SX CMT
DVT		1993		WITH 500 SX CMT
PROD	4.5	4529	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2010 11:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: RUN TBG TO 4400', PUMP 15 SX. GEL FOLLOWED BY 30 SX 60/40 4% W 150# HULLS. PULL TBG TO 2000' AND CIRCULATE CEMENT TO SURFACE. CHECK 8 5/8 W 50 SX.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 06/29/2010 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO 4400' & PUMPED 15 SX GEL THEN 50 SX CMT WITH 150# HULLS. 1ST PLUG PULLED TBG TO 2005' & PUMPED 130 SX CMT WITH 200# HULLS. 2ND PLUG PULLED TBG TO 1058' & CIRCULATED CMT TO SURFACE WITH 160 SX CMT. TOPPED OFF 4 1/2" WITH 60 SX CMT BUT CMT CONTINUED TO FALL. PRESSURED BACKSIDE TO 200# WITH 80 SX CMT. 6/29/10: TOPPED OFF 4 1/2" WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4529	4535		OH

INVOICED
DATE 10-14-2010
INV. NO. 2011 06 0021

RECEIVED
JUL 21 2010

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED

JUL 14 2010

KCC DODGE CITY

Form CP-203