

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21052-00-00
Spot: SESENE Sec/Twnshp/Rge: 28-15S-27W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: SARALEE Well #: 1
County: GOVE Total Vertical Depth: 4279 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	342	0	250 SX
PROD	5.5	4278	0	250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2010 11:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 400 sxs cement and 400# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2010 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 342' w/250 sxs cement.
5 1/2" production casing set at 4278' w/250 sxs cement.
DV Tool at 1854' w/550 sxs.
Junk in hole at 3739'.
Ran tubing to 3701' - pumped 15 sxs gel - 75 sxs cement mixed with 200# hulls.
Pulled tubing to 1900' - pumped 100 sxs cement mixed with 100# hulls.
Pulled tubing to 824' - pumped 100 sxs cement mixed with 100# hulls.
Pulled tubing to 412' - pumped 30 sxs cement - cement to surface.
Pulled tubing to surface. Topped production casing with 6 sxs cement.
Connected to 8 5/8" surface casing - pumped 12 sxs cement.
Max. P.S.I. 300#.

Perfs:

Top	Bot	Thru	Comments
3874	3884		
3843	3848		
3834	3836		
3811	3816		
3722	3728		
3628	3638		

INVOICED
DATE 10-14-2010
INV. NO. 2011060021

Remarks: ALLIED CEMENTING COMPANY-TICKET #36712.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

RECEIVED

JUL 15 2010

Form CP-2/3

JUL 06 2010

KCC WICHITA

BEREXCO INC.-BEREN CORPORATION
WICHITA, KS 67202

28-15 -27W
SE SE NE

#1 SARALEE

site: 5-1/2 N & 1/2 E OF PENDENNIS, KS	city: GOVE	API 15-063-21052
contr: BEREDCO, INC.	field: ROSA NW	
geol: P. SAM HOUSTON		
fr date 08/07/86	spd date 08/07/86	drig comp 08/16/86
		card issued 12/18/86
		last revised 01/25/89

ELV: 2415 KB LOG	
tops.....	depth/datum
ANH.....	1855 +560
B/ANH.....	1890 +525
HEEB.....	3606 -1191
LANS.....	3645 -1230
STARK.....	3893 -1478
BKC.....	3949 -1534
MARM.....	3974 -1559
PAW.....	4093 -1678
FT SC.....	4145 -1730
CHER.....	4171 -1756
MISS.....	4250 -1835
PBD.....	4213 -1798
LTD.....	4279 -1864

IP status:
OIL, P 51 BO & 57 BWP, LKC 3834-3884 OA,
 RTD.....4280 -1865
 INFO RELEASED: 1/25/89 - WAS OIL WELL - TIGHT HOLE
 CSG: 8 5/8" 342 / 250 SX, 5-1/2" 4278 / 250 SX, DV
 TOOL AT 1854 / 50 SX
 NO CORES
 DST (1) 3614-3640 (SHAW), / 60-60-60-60, REC 100'
 HOCM (40% OIL) ISIP 986# FSIP 966# IFP 50# -50#
 FFP 71# -71#
 DST (2) 3721-3737 (LKC), / 45-45-45-45, REC 280' OIL,
 276' MW (CHL 28,000 PPM) ISIP 1154# FSIP 1134#
 IFP 50# -162# FFP 182# -264#

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

BEREXCO INC.-BEREN CORPORATION
WICHITA, KS 67202

28-15 -27W
SE SE NE

#1 SARALEE

DST (3) 3794-3827 (LKC), / 30-30-30-30, REC 5' OCM, 45' M ISIP 818# FSIP 668# IFP 29#
 -39# FFP 49# -50#
 DST (4) 3824-3858 (LKC), / 45-45-45-45, 200' GIP, REC 900' OIL (GR 41), 60' OCM, 5' MW
 ISIP 828# FSIP 650# IFP 69# -216# FFP 265# -334#
 DST (5) 3862-3888 (LKC), / 45-45-45-45, 270' GIP, REC 540' OIL (GR 40), 180' W (CHL 39,000
 PPM) ISIP 324# FSIP 324# IFP 127# -236# FFP 265# -295#
 DST (6) 4108-4180 (MARM, CHER), / 30-30-30-30, REC 30' M ISIP 749# FSIP 255# IFP 59#
 -59# FFP 69# -69#
 MICT - CO, PF (LKC) 3874-3884, W / 2 SPF, AC 500 GAL (MCA) & 1200 GAL (28% NE HCL),
 GSO, PF (LKC) 3834-3836 & 3843-3848, W / 4 SPF, AC 500 GAL (15% INS), GSO, SET 2-3/8"
 TBG AT 4211, POP, P 51 BO & 57 BWP (GR 39.2), 9/9/86