

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22449-00-00
Spot: NENENE Sec/Twnshp/Rge: 3-10S-25W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: SHOEMAKER Well #: 1
County: GRAHAM Total Vertical Depth: 4080 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	291	0	w/unknown sxs cmt
T1	2.375	3940		
PROD	4.5	4079	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2010 10:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 7 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2010 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3900' - pumped 7 sxs gel - followed with 90 sxs cement and 300# hulls.
Pulled tubing to 1802' - pumped 100 sxs cement - good circulation of cement.
Pulled tubing out - topped off with 40 sxs cement.
Tied onto backside - pumped 5 sxs cement.
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3990	3998		
3967	3972		
3922	3926		
3912	3916		
3532	3545		
3514	3517		

INVOICED
DATE: 10-14-2010
INV. NO: 2011060021

RECEIVED
JUL 01 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #35085A.

Plugged through: TBG

District: 04

Signed Macmill
(TECHNICIAN) CM

replacement card

3-10 -25W
NE NE NE

T-L ENERGY COMPANY
MORLAND, KS 67650

#1 SHOEMAKER

API 15-065-22449

site: 8-1/2 S & 1/2 W OF MORLAND, KS
contr: LLOYD DRILLING COMPANY
geol: CHUCK RHOADES
fr date 04/11/88

city: GRAHAM
field: EMOR

spd date 04/16/88 drlg comp 04/25/88 card issued 11/16/88 last revised 04/05/89

ELV: 2551 KB LOG

tops.....	depth/datum
ANH.....	2180 +371
B/ANH.....	2212 +339
HOW.....	3423 -872
TOP.....	3574 -1023
HEEB.....	3789 -1238
TOR.....	3814 -1263
LANS.....	3832 -1281
BKC.....	4059 -1508
LTD.....	4083 -1532

IP status:
OIL, P 6 BO & 2 BWPD, LKC 3832-3998 OA,
 INFO RELEASED: 4/5/89 - WAS OIL WELL - TIGHT HOLE
 CSG: 8-5/8" 229, 4-1/2" 4079 / 100 SX, MULTI STAGE
 COLLAR AT 2118 / 275 SX
 NO CORES
 DST (1) 3815-3842 (TOR), / 30-30-30-30, (1ST OP) WB,
 DIED / 8", (2ND OP) NB, 120' GIP, REC 20' OIL SPTS M
 (5% OIL, 95% M) ISIP 65# FSIP 54# IFP 54# -54# FFP
 54# -54# IHP 1942# FHP 1921# BHT 117 °
 DST (2) 3880-3920 (LKC), / 60-60-60-90, (1ST OP) STDY
 BLO INCR TO 6 INCH, (2ND OP) STDY BLO INCR 5 INCH,
 470' GIP, REC 58' OC GSY M (20% OIL, 30% G, 50% M)
 ISIP 185# FSIP 196# IFP 43# -43# FFP 43# -43# IHP
 2019# FHP 1997# BHT 119 °

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)