

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-30173-00-00  
Spot: E2W2NWSE Sec/Twnshp/Rge: 12-17S-21W  
1980 feet from S Section Line, 2130 feet from E Section Line  
Lease Name: VAN WINKLE Well #: 1  
County: NESS Total Vertical Depth: 4110 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	401		WITH 275 SX CMT
DVT		1424		WITH 400 SX CMT
PROD	5.5	4107	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2010 12:00 PM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: SPOT 25 SX CMT @ 3600'. CIRCULATE CMT TO SURFACE FROM 1425'. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/28/2010 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 50# HULLS & 25 SX CMT AT 3613'. 1ST PLUG PULLED TBG TO 1425' & PUMPED 250# HULLS, 160 SX CMT WITH DIMINISHING RETURNS. 2ND PLUG PULLED TBG TO 695' & CIRCULATED CMT TO SURFACE WITH 35 SX CMT. 3RD PLUG PTOOH & BULLHEADED 5 1/2" WITH 15 SX CMT. PRESSURED TO 200#. CMT CONTINUED TO FALL. PRESSURED BACKSIDE TO 400# WITH 6 SX CMT. 6/29/10: TOPPED 5 1/2" WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4054	4056		
4046	4049		

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060021

RECEIVED  
JUL 21 2010  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
JUL 14 2010  
KCC DODGE CITY

Form CR-23